BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/06/12-13 Date: 11.02.2013 **Item No:**

SCHEDULE-B

NAME OF WORK:Improvements of drains at Maheshwarinagara & Kempegowda nagar 6th 'B' Cross R/S in Dasarahalli w no.15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **N SHIVANANDA**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	9
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	443.40	80.0	Rupees Eighty Only	35472.00
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	39.56	3600.0	Rupees Three Thousand Six Hundred Only	142416.00
3	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating curing and necessary steel or ply wood or plank centering and form work etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for beams, columns, staircase and roof with M-20(Cement-320 kg/cum) complete as per specifications.	Cum	105.48	5450.0	Rupees Five Thousand Four Hundred Fifty Only	574866.00
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	63.00	7100.0	Rupees Seven Thousand One Hundred Only	447300.00
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	1054.80	290.0	Rupees Two Hundred Ninety Only	305892.00

Signature of the Contractor

Executive Engineer
Dasarahalli Division.

6	Supplying and fixing precast rainforced concee slab 1 cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per specifications.	Sqm	263.70	1550.0	Rupees One Thousand Five Hundred Fifty Only	408735.00
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. complete as per specifications.	Cum	443.40	75.0	Rupees Seventy Five Only	33255.00
					Total	1947936.00
					Percentage	-2.07%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,